
PUBLIC WORKS DEPARTMENT

UTTARAKHAND



NAME OF CIRCLE	:-	8rth Circle, New Tehri
District	:-	Tehri garhwal
Division	:-	C.D. PWD. Chamba
Assembly	:-	Tehri garhwal
Constituency	:-	Dhnaulyti
Block	:-	Thauldhar
Name of fund	:-	Daviya Apda
Name of Work		Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwarna road, in the Distt- Tehri garhwal, Block Thauldhar.
	:-	
Cost of Work	:-	8.69 lac
Category of Road / Length	:-	VR / 5 km
Divisional Segment ID of Road	:-	5549

||

INDEX OF CONTENT

SL NO.	CONTENTS	Page No.	
		From	To
1	Title Page	1	
2	Index	2	
3	List of Officers	3	
4	Report	4	
5	Reference and Certificates		
6	Specification		
7	Analysis of Rates		
8	Details of measurements		
9	Bill of Quantity		
10	Summary of Estimated Cost		
11	Photographs		
12	Drawings		

Name of Officers Preparing the Estimate

Sl.No.	Name	Designation	Signature
1	Er. Jagdish Singh	Executive Engineer	
2	Er. Amit Rusiya/Maneesha Sethi	Assistant Engineer	
3	Er. Ajendra Singh/Vineet Saini	Addl. Assistant Engineer	
4	Er. Reeta Negi	Addl. Assistant Engineer (T)	

प्रतिवेदन

कार्य का नाम:—	Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwarna road, in the Distt- Tehri garhwal, Block Thauldhar.
जनपद का नाम:—	Tehri garhwal
विधानसभा का नाम:—	Dhnaulyti
विकासखण्ड का नाम:—	Thauldhar
मार्ग की श्रेणी एवं लम्बाई:—	VR / 5.00 km
कार्य की लागत:—	8.69 lac
प्रेषित कार्य की विस्तृत आख्या:—	जनपद टिहरी गढ़वाल के विधानसभा क्षेत्र धनोल्ती में कमांद ज्वारना मोटर मार्ग जिसकी कुल लम्बाई 17.200 कि०मी० है, यह मार्ग निर्माण खण्ड, लो०नि०वि० चम्बा के अधीन पड़ता है। अत्यधिक भारी वर्षा के कारण उक्त मोटर मार्ग के किमी० 5 चैनेज 4.925, 4.950, 4.975 में दीवारें क्षतिग्रस्त हो गई हैं। उक्त क्षतिग्रस्त स्थानों पर दीवारें क्षतिग्रस्त होने से मार्ग की चौड़ाई भी कम हो गयी है जिस कारण मोटर मार्ग के उक्त स्थान पर वाहनों का आगमन असुरक्षित हो गया है तथा किसी भी समय कोई भी अप्रिय घटना घटित होने की प्रबल संभावना बनी हुयी है। जिस कारण मार्ग पर सुगम एवं सुरक्षित यातायात की सुरक्षा हेतु उक्त स्थानों पर दीवारों का निर्माण किया जाना अतिआवश्यक है।
प्राविधान	1- Excavtion work for Foundation 2. Plum Concrete in 1:3:6 3. Retaining Wall in RR 1:6 4. Weep Hole work 5. HPS Filling
दरें:—	आगणन में सभी दरें प्रमुख अभियन्ता लोक निर्माण विभाग देहरादून के द्वारा के स्वीकृत शैड्यूल ऑफ रेट दिनांक 24.08. 2024 के आधार पर लगाई गयी है।

अतः उपरोक्तानुसार रु 8.69 लाख मात्र का आगणन गठित कर आवश्यक स्वीकृति हेतु प्रेषित है।

सहायक अभियन्ता
निर्माण खण्ड, लो०नि०वि०, चम्बा
टिहरी गढ़वाल।

अधिशाली अभियन्ता
निर्माण खण्ड, लो०नि०वि०, चम्बा
टिहरी गढ़वाल।

प्रमाणपत्र

वित्तीय वर्ष 2025-26 में अनु० सं०- 22, लेखाशीर्षक - 5054,

Name of work :-Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwana road, in the Distt- Tehri garhwal, Block Thauldhar.

आगणन गठित करने वित्तीय मितव्ययता का पूर्णतः पालन किया गया है, अपरिहार्य एवं आवश्यक कार्यों को ही आगणन में सम्मिलित किया गया है, किसी प्रकार का गैर जरूरी वित्तीय एवं भौतिक प्राविधान आगणन में सम्मिलित नहीं किये गये है।

सहायक अभियन्ता
निर्माण खण्ड लो०नि०वि०,
चम्बा (टिहरी गढवाल)।

अधिशाली अभियन्ता,
निर्माण खण्ड लो०नि०वि०,
चम्बा (टिहरी गढवाल)।

प्रमाणपत्र

वित्तीय वर्ष 2025-26 में अनु० सं०- 22, लेखाशीर्षक - 5054,

Name of work :-Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwana road, in the Distt- Tehri garhwal, Block Thauldhar.

उक्त पुर्ननिर्माण कार्य जनयातायात की दृष्टि से कराया जाना अत्यन्त आवश्यक एवं अपरिहार्य है, जिसकी स्वीकृति प्राप्त होने पर कार्य इसी वित्तीय वर्ष में पूर्ण कर लिया जायेगा।

सहायक अभियन्ता
निर्माण खण्ड लो०नि०वि०,
चम्बा (टिहरी गढवाल)।

अधिशाली अभियन्ता,
निर्माण खण्ड लो०नि०वि०,
चम्बा (टिहरी गढवाल)।

प्रमाणपत्र

वित्तीय वर्ष 2025-26 में अनु० सं०- 22, लेखाशीर्षक - 5054,

Name of work :-Re-Construction of retaining wall at km 1.00 ch-0.850 on
Kamand Jwana road, in the Distt- Tehri garhwal, Block Thauldhar.

सहायक अभियन्ता
निर्माण खण्ड लो०नि०वि०,
चम्बा (टिहरी गढवाल)।

अधिशाली अभियन्ता,
निर्माण खण्ड लो०नि०वि०,
चम्बा (टिहरी गढवाल)।

प्रमाणपत्र

वित्तीय वर्ष 2025-26 में अनु० सं०- 22, लेखाशीर्षक - 5054,

Name of work :-Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwana road, in the Distt- Tehri garhwal, Block Thauldhar.

उक्तवर्णित कार्य रु 19.57 लाख हेतु वांछित धनराशि, न तो जिलाधिकारी से प्राप्त हुई है, और न ही अन्य योजओं/संस्थाओं से प्राप्त की संभावना है।

सहायक अभियन्ता
निर्माण खण्ड लो०नि०वि०,
चम्बा (टिहरी गढवाल)।

अधिशाली अभियन्ता,
निर्माण खण्ड लो०नि०वि०,
चम्बा (टिहरी गढवाल)।

प्रमाणपत्र

वित्तीय वर्ष 2025-26 में अनु० सं०- 22, लेखाशीर्षक - 5054,

Name of work :-Name of work :-Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwara road, in the Distt- Tehri garhwal, Block Thauldhar.

प्रमाणित किया जाता है कि उक्त कार्य, वित्तीय वर्ष 2025-26 की दैवीय आपदा से क्षतिग्रस्त हुआ है तथा कार्य की क्षति की रिपोर्ट जिलाधिकारी कार्यालय (आपदा प्रबन्धन) एवं राज्य आपदा प्रबन्धन विभाग को भी सूचित करायी गई है, विभागीय सम्पत्ति की क्षति (दैवीय आपदा/बाढ़ व भूस्खलन वित्तीय वर्ष 2025-26 के कारण) का फोटोग्राफ भी गठित आगणन में संलग्नकर प्रेषित किये गये है।

सहायक अभियन्ता
निर्माण खण्ड लो०नि०वि०,
चम्बा (टिहरी गढवाल)।

अधिशाली अभियन्ता,
निर्माण खण्ड लो०नि०वि०,
चम्बा (टिहरी गढवाल)।

प्रमाण पत्र

कार्य का नाम :— Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwara road, in the Distt- Tehri garhwal, Block Thauldhar.

प्रमाणित किया जाता है कि बाढ़ एवं भूस्खलन के अन्तर्गत धनोल्टी विधानसभा के अन्तर्गत क्षतिग्रस्त मार्ग पर हुई क्षतियां भारत सरकार के दिशा-निर्देशों के बिन्दु संख्या 9 (1) से आच्छादित है, जिसका मेरे द्वारा स्थलीय निरीक्षण कर लिया गया है। निर्माण कार्य हेतु कार्यस्थल पर पत्थर उपलब्ध नहीं है। हिल साइड में स्लाइड जोन बनने के कारण हिल साइड में पहाड कटान का कार्य किया जाना संभव नहीं है।

सहायक अभियन्ता
निर्माण खण्ड, लो0नि0वि0, चम्बा
टिहरी गढवाल।

अधिशाली अभियन्ता
निर्माण खण्ड, लो0नि0वि0, चम्बा
टिहरी गढवाल।

xzkeh.k ekxZ@2-55 fdeh0

विशिष्टियाँ

Name of work Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwarna road, in the Distt- Tehri garhwal, Block Thauldhar.

समस्त कार्य लोक निर्माण विभाग की विस्तृत विशिष्टियों एवं प्रमुख अभियंता, लोक निर्माण विभाग, देहरादून द्वारा समय-समय पर जारी परिपत्रों के अनुसार सम्पादित कराये जायेंगे ।

AAE
C.D.P.W.D. Chamba

AE
C.D.P.W.D. Chamba

EE
C.D.P.W.D. Chamba

ANALYSIS OF RATES

Name of work: **Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwarna road, in the Distt- Tehri garhwal, Block Thauldhar.**

S.N.	Item of Work	UNIT	RATE	SOR 24-25
1	Excavation in foundation for retaining, breast walls etc, in all types of soils and rocks including all lead, lift and disposal of surplus material as per direction of engineer - in - charge, as per drawing and technical specifications Clause 305.1 of MORD Specifiction	Cum	419.70	Misc '1-2
2	Cement plumMasonrywith 40% plum& 60% 1:3:6 cement concrete including supply of all material, labour, T&P etc. required for proper completion of the work as per drawings and technical specifications Clause 802, 803, 1202 & 1203 of MORD Specifiction	Cum	3931.00	Misc 2--1
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	Rmt	181.60	Mord 12-9
4	Random Rubble Stone Masonry laid in 1:6 cement and sand mortar, in breast walls, retaining walls, parapets, scuppers, etc. including supply of all material, labour, T&P and royalties etc. complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 of MORD Specifiction	Cum	4000.30	Misc '1-4
5	Random Rubble Stone Masonry laid Dry, in breast walls, retaining walls,etc. including supply of all material, labour, T&P and royalties etc.complete as per drawing and technical specifications Clauses 702, 704,1202 & 1203 of MORD Specifiction	Cum	2317.60	Misc '1-3
6	Hand Packed stone filling in back of wallls including cost of all materials, royalty, T&P etc. complete as per direction of Engineer-in-charge. (As per PWD Uttarakhand specifications)	Cum	1063.30	Misc '1-5

AAE
C.D.P.W.D. Chamba

AE
C.D.P.W.D. Chamba

EE
C.D.P.W.D. Chamba

Addl. Asst. Engineer
CD PWD Chamba

Assistant Engineer
CD PWD Chamba

Executive Engineer
CD PWD Chamba

Detail of measurement

Name of work:-				Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwarna road, in the Distt- Tehri garhwal, Block Thauldhar.						
SI No.	Item of Work	No.			L	B	H	Qty		
1	Excavation in foundation for retaining, breast walls etc, in all types of soils and rocks including all lead, lift and disposal of surplus material as per direction of engineer - in - charge, as per drawing and technical specifications Clause 305.1 of MORD Specifiction									
	T/Wall 1st Step Ch 4.975	1	X	1/2	18.00	1.50	1.50	20.25	Cum	
	T/Wall 2nd Step Ch 4.975	1	X	1/2	18.00	1.50	1.00	13.50	Cum	
	R/Wall Ch 4.975	1	X	1/2	18.00	1.77	1.75	27.88	Cum	
	R/Wall Ch 4.950	1	X	1/2	8.00	1.77	1.75	12.39	Cum	
	R/Wall Ch 4.925	1	X	1/2	10.00	1.60	1.50	12.00	Cum	
							Total	86.02	Cum	
2	Cement plumMasonrywith 40% plum& 60% 1:3:6 cement concrete including supply of all material, labour, T&P etc. required for proper completion of the work as per drawings and technical specifications Clause 802, 803, 1202 & 1203 of MORD Specifiction									
	T/Wall 1st Step Ch 4.975	1	X	1	18.00	(1.50 +1.00)1/2	1.50	33.75	Cum	
	T/Wall 2nd Step Ch 4.975	1	X	1	18.00	(1.50 +1.00)1/2	1.50	33.75	Cum	
							Total	67.50	Cum	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7									
	T/Wall- 1st Step-X/Sec 93/31 @ 1.50 mtr C/C	2	X	13	1.50			39.00	Rmt	
							Total	39.00	Rmt	
4	Random Rubble Stone Masonry laid in 1:6 cement and sand mortar, in breast walls, retaining walls, parapets, scuppers, etc. including supply of all material, labour, T&P and royaltiies etc. complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 of MORD Specifiction									
	R/Wall Ch 4.975									
	Bottom Band	1	X	1	18.00	(1.77 +1.57)1/2	0.60	18.04	Cum	
	top Band	1	X	1	18.00	(0.80 +0.60)1/2	0.60	7.56	Cum	
	Vertical Band	1	X	7	0.60	(1.57 +0.80)1/2	2.30	11.45	Cum	
	R/Wall Ch 4.950									
	Bottom Band	1	X	1	8.00	(1.77 +1.57)1/2	0.60	8.02	Cum	
	top Band	1	X	1	8.00	(0.80 +0.60)1/2	0.60	3.36	Cum	
	Vertical Band	1	X	3	0.60	(1.57 +0.80)1/2	2.30	4.91	Cum	
	Total						Total	53.33	Cum	
5	Random Rubble Stone Masonry laid Dry, in breast walls, retaining walls,etc. including supply of all material, labour, T&P and royaltiies etc.complete as per drawing and technical specifications Clauses 702, 704,1202 & 1203 of MORD Specifiction									
	R/Wall Ch 4.975	1	X	1	18.00	(1.77 +0.60)1/2	3.50	74.66	Cum	
	Deduction							(37.05)	Cum	
	R/Wall Ch 4.950	1	X	1	8.00	(1.77 +0.60)1/2	3.50	33.18	Cum	
	Deduction							(16.29)	Cum	
	R/Wall Ch 4.925	1	X	1	10.00	(1.57 +0.60)1/2	3.00	32.55	Cum	
							Total	87.05	Cum	
6	Hand Packed stone filling in back of wallls including cost of all materials, royalty, T&P etc. complete as per direction of Engineer-in-charge. (As per PWD Uttarakhand specifications)									
	R/Wall Ch 4.975	1	X	1/3	18.00	0.60	1.75	6.30	Cum	
	R/Wall Ch 4.950	1	X	1/3	8.00	0.60	1.75	2.80	Cum	
	R/Wall Ch 4.925	1	X	1/3	10.00	0.60	1.50	3.00	Cum	
							Total	12.10	Cum	

AAE
C.D.P.W.D. Chamba

AE
C.D.P.W.D. Chamba

Addl. Asst. Engineer
CD PWD Chamba

Assistant Engineer
CD PWD Chamba

Bill of Quantity

Name of work:- Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwarna road, in the Distt- Tehri garhwal, Block Thauldhar.

S. No.	Item	Qty.	Unit	Rate	Amount
1	Excavation in foundation for retaining, breast walls etc, in all types of soils and rocks including all lead, lift and disposal of surplus material as per direction of engineer - in - charge, as per drawing and technical specifications Clause 305.1 of MORD Specifiction	86.02	Cum	419.70	36102.59
2	Cement plumMasonrywith 40% plum& 60% 1:3:6 cement concrete including supply of all material, labour, T&P etc. required for proper completion of the work as per drawings and technical specifications Clause 802, 803, 1202 & 1203 of MORD Specifiction	67.50	Cum	3931.00	265342.50
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	39.00	Rmt	181.60	7082.40
4	Random Rubble Stone Masonry laid in 1:6 cement and sand mortar, in breast walls, retaining walls, parapets, scuppers, etc. including supply of all material, labour, T&P and royaltiies etc. complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 of MORD Specifiction	53.33	Cum	4000.30	213348.00
5	Random Rubble Stone Masonry laid Dry, in breast walls, retaining walls,etc. including supply of all material, labour, T&P and royaltiies etc.complete as per drawing and technical specifications Clauses 702, 704,1202 & 1203 of MORD Specifiction	87.05	Cum	2317.60	201751.72
6	Hand Packed stone filling in back of wallls including cost of all materials, royalty, T&P etc. complete as per direction of Engineer-in-charge. (As per PWD Uttarakhand specifications)	12.10	Cum	1063.30	12865.93
	G TOTAL				7,36,493.14

AAE
C.D.P.W.D. Chamba

AE
C.D.P.W.D. Chamba

EE
C.D.P.W.D. Chamba

Addl. Asst. Engineer
CD PWD Chamba

Assistant Engineer
CD PWD Chamba

Executive Engineer
CD PWD Chamba

ABSTRACT OF COST

Name of work:- Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwarna road, in the Distt- Tehri garhwal, Block

S.N.	ITEM OF WORK	AMOUNT (in Rs)
1	Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwarna road, in the Distt- Tehri garhwal, Block Thauldhar.	7,36,493.14
2	Add 18 % G.S.T.	1,32,568.77
	G Total	8,69,061.91
	SAY Rs in Lacs	8.69

AAE
C.D.P.W.D. Chamba

AE
C.D.P.W.D. Chamba

EE
C.D.P.W.D. Chamba

Name of work-	Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwarna road, in the Distt- Tehri garhwal, Block Thauldhar.
----------------------	---

AAE
C.D.P.W.D. Chamba

AE
C.D.P.W.D. Chamba

EE
C.D.P.W.D. Chamba

Name of work-	Re-Construction of retaining wall at km 1.00 ch-0.850 on Kamand Jwarna road, in the Distt- Tehri garhwal, Block Thauldhar.
----------------------	---

AAE
C.D.P.W.D. Chamba

AE
C.D.P.W.D. Chamba

EE
C.D.P.W.D. Chamba